

INVITATION FOR QUOTATIONS FOR “Shindaone drainage improvement works”

To

Date: 01/03/2018

Dear Sir/ Madam,

Sub: **INVITATION FOR QUOTATION FOR “Shindaone drainage improvement works”**

1. You are invited to submit your most competitive quotation for the following works.

Brief Description	Specifications and scope	Quantity	Delivery Period	Place of Delivery
Providing and laying RCC Hume (including PVC) pipeline for drainage in Shindaone village, with chambers and all allied necessary works as may be necessary and mentioned	Specifications 1. Providing, laying and joining best quality RCC Hume pipes (class NP2; sizes mentioned in BOQ) with all specials below ground at all depths, including cutting, joining with hump yarn and cement mortar (1:1), and testing and excavation and refilling complete (in all strata). 2. Providing and constructing brick masonry Inspection Chambers up-to necessary depth (1.5 m depth) of size 0.9 m * 0.6 m, in 0.23 m thick brick masonry in cement mortar (1:5), cement plastering inside and outside faces with neat cement rendering to internal surfaces, haunches, channels including Cast Iron heavy duty frame and cover fixed in cement concrete (1:2:4) and three coats of bituminous paint to frame and cover including excavation and refilling complete.	Details given in Bill of Quantities in Annexure	15 days from date of release of Work Order	Shindaone, Taluka Haveli, Pune

	<p>Scope</p> <ol style="list-style-type: none"> 1. Full excavation and refilling in all kinds of strata, providing and laying, joining, cutting etc. of pipes with all necessary joints and specials and necessary material. 2. Provision of all required resources and facilities as in labor, skilled and unskilled human-power (with their lodging and boarding, if required), electricity, water etc. 3. Ensuring compliance to all standards asked for in this document and all government standards and norms regarding the nature of works. 4. Ensuring best quality work. 5. Ensuring water flow all throughout the laid pipeline with required/adequate velocity/ discharge. <p>Details given in BOQ given in Annexure A.</p>			
--	--	--	--	--

2. **Quotation**

- a) The contract shall be for the full quantity as described above. Corrections, if any, shall be made by crossing out, initialing, dating and re writing.
- b) All duties, taxes and other levies payable on the raw materials and components shall be included in the total price. Parties are requested to submit quotation strictly in the format provided.
- c) Sales tax in connection with the sale shall be shown separately.
- d) The rates quoted by the parties shall be fixed for the duration of the contract and shall not be subject to adjustment on any account.
- e) Delivery, transportation of construction material at submitting parties' cost.
- f) The Prices shall be quoted in Indian Rupees only.

3. Each party must submit only one quotation for the works.

4. **Validity of Quotation**

Quotation shall remain valid for a period not less than 60 days after the deadline date specified for submission.

5. **Evaluation of Quotations**

BAIF will evaluate and compare the quotations determined to be substantially responsive i.e. which

- (a) are properly signed; and
- (b) confirm to the terms and conditions, and specifications.

The quotations would be evaluated for all the items together.

6. **Award of contract**

BAIF will award the contract to the party whose quotation has been determined to be substantially responsive, suit to the application and who has offered the lowest evaluated quotation price. The quotations should include GST registration No/PAN No.

- 6.1 Notwithstanding the above, BAIF reserves the right to accept or reject any quotations and to cancel the purchase process and reject all quotations at any time prior to the award of contract.
- 6.2 The party whose offer is accepted will be notified of the award of contract by BAIF prior to expiration of the quotation validity period. The terms of the accepted offer shall be incorporated in the purchase order/ work order.
- 6.3 No advance payment is possible for works; parties are requested to read the payment terms carefully. 95% of the payment shall be released after work completion. Remaining 5% shall be released at the end of monsoon or September, 2018; whichever is earlier. The party shall rectify any deviation or defect found in works within this period that comes under the parties' scope. Not fulfilling the criteria, 5% amount retained shall be taken up for all remedial works.
- 7. Normal commercial warranty/ guarantee shall be applicable to the supplied goods and works. The items in Bill of Quantities are approximate estimate of works. The parties are requested to give running meter cost for laying pipeline considering the length as given and material required for the same. However, it may so happen that the quantity of actual physical work done deviates from what is mentioned in BOQ. Payment shall be done strictly against the invoice presented by the selected party, which shall be duly verified by BAIF appointed supervisor for payment.
- 8. You are requested to provide your offer **on or before 7th March, 2018, 1400 hours**, in the name of **BAIF Development Research Foundation** only.
- 9. We look forward to receiving your quotations and thank you for your interest in this project.

BAIF Development and Research Foundation

Authorized Signatory

ANNEXURE A
BOQ (Quotation format)

VILLAGE : Shindaone					
NAME OF WORK : DRAINAGE IMPROVEMENT WORK					
BILL OF QUANTITIES					
SUMMARY STATEMENT :-					
(A) SANITARY & DRAINAGE WORKS				RS	
GRAND TOTAL					
NO.	DESCRIPTION OF WORK	Quantity	UNIT	RATE	AMOUNT
(A)	SANITARY & DRAINAGE WORKS				
A-1	EXCAVATION FOR FOUNDATION				
	in all types of soil, including refilling around foundations & in plinth with selected excavated earth in 200 mm thick layers, watering, consolidating etc. & disposing off surplus earth by spreading at site as directed, complete.				
	a) In earth all types of soil and soft murum	43.20	CUM		
	b) In hard rock by machine	87.12	CUM		
A-2	Providing, laying & jointing best quality R.C.C. HUME PIPE with all specials below ground at all depth including cutting, jointing with hump yarn, and cement mortar (1:1) and testing and including refilling complete.(NP2 class)				
	a) 250 mm dia	120.00	RM		
	b) 200 mm dia	242.00	RM		
A-3	Providing & constructing brick masonry INSPECTION CHAMBERS upto 900 mm / 1500 mm / 1800 mm depth in 230 mm thick brick masonry in c.m. (1:5) cement plastering inside and outside faces with neat cement rendering to internal surfaces, haunches, channels, including RCC Heavy duty frame and cover fixed in cement concrete 1:2:4 & 3 coats of bituminous paint to frame and cover including excavation and refilling complete.				
	c) SIZE : 900 mm *600 mm upto 1500 mm depth	30.00	NO		
A-4	Providing and laying PVC pipes in best quality with all allied works for household connection to chambers (approx quantity)	1000.00	RM		
	SUB TOTAL IN RS				
	ADD FOR CONTINGENCIES (%)				
	GRAND TOTAL				
	ADD GST (18%)				
	TOTAL AMOUNT WITH TAXES (Round off)				
	In words				

Terms and conditions:

1. Terms of payment: 95% after construction and laying of all pipeline works and rest after three months of work completion.
1. Work completion; 15 days from date of release of Work Order
2. Location: Shindaone village
3. Validity of quotation: 60 days
4. GST registration no. (Enclose copy)
5. Permanent Account Number (Enclose copy)

Note; please mention terms and conditions along with offer