



BISLD/BAIF MP

State Office: Madhya Pradesh

E-7/226 Bharat Nagar Road, Near Dhanvantri Complex, Arera Colony, Bhopal 462016
Madhya Pradesh, India

Phone +91 0755-2561580 E-mail: baifmp@gmail.com bisld.mp@baif.org.in

CIN: U73200PN2012NPL142984

**INVITATION FOR QUOTATION FOR CONSTRUCTION OF PERMANENT CHECK DAM IN
HDFC HRDPPROJECT, RAMA BLOCK, JHABUA DISTRICT OF MP**

O. No. __BISLD/Bhopal MP/2022-23/48

Date: 23/11/2022

To,

.....
.....

Sub: Invitation for Quotation

Dear Sir / Madam,

You are invited to submit a competitive quotation for the following tender:

Brief description of the tender:

Construction of Permanent Check Dam in Rama Block, Jhabua Dist, Madhya Pradesh

1. Quoted Price:

- a. The Quotation shall be valid for one Month for the above described work.
- b. The bidder shall quote for goods/services in the attached format of quotation.
- c. All duties, taxes, F.O.R. and other levies payable by the bidder, shall be included in the goods/services and shall stand final.
- d. The rates quoted for each goods/service shall be fixed for the duration of the validity of the quotation and shall not be subject to adjustment.
- e. Corrections if any, shall be made by crossing out, initialing, dating and rewriting.
- f. The prices shall be quoted in Indian Rupees only

2. Each bidder must submit only one quotation. The Bidder shall not contact other bidders in matters relating to this Quotation.

3. Validity of Quotation:

The quotation shall remain valid for one Month after the deadline fixed for submission of quotation.

4. Evaluation of Quotation:

Purchaser will evaluate and compare the quotations determined to be substantially responsive i.e. which are properly signed and conform to the terms and conditions and specifications in the following manner:

- a. The evaluation will be done for all the goods/services put together. The items for which no rates have been quoted will be treated as zero and the total amount will be computed accordingly. We will award the contract to the responsive bidder whose total cost for all the items put together is the lowest.
- b. Compare terms & conditions and specifications



BISLD/BAIF MP

State Office: Madhya Pradesh

E-7/226 Bharat Nagar Road, Near Dhanvantri Complex, Arera Colony, Bhopal 462016

Madhya Pradesh, India Phone +91 0755-2561580

E-mail: baifmp@gmail.com bisld.mp@baif.org.in

CIN: U73200PN2012NPL142984

Award of Contract:

- a. Organization will award the contract to the bidder whose quotation has been determined to be substantially responsive and who has offered the lowest price.
 - b. Organization prior to the expiration of the quotation validity period will notify the bidder whose quotation is accepted for the award of contract. The terms of the accepted offer shall be incorporated in the Work Order.
 - c. Notwithstanding the above, the organization reserves the right to accept or reject any quotation and to cancel the bidding process and reject all quotations at any point of time prior to the award of the contract.
5. Payment shall be made immediately within 15 days after completion of the work. The 1st RA Bill after completion of 25% work and 2nd RA bill after completion of 70% work and remaining 5% after final completion of the work. If the party fails to complete the work within the timeline, then the organization will deduct the amount as penalty as per the decision of the BAIF Management.
6. Normal commercial guarantee/warranty shall be applicable to the supplied goods/ services.

7. Submission of Quotations:

Please submit the quotation in a sealed envelope as mentioned above.

- **Last date of Submission is __30/11/22 by 2 pm.**

We look forward to receiving your quotations.

Yours sincerely

V.B. Dyasa
(V.B. Dyasa)

Regional Director
West Region

**FORMAT FOR
QUOTATION**

Sr. No.	Description of Service/Goods/Items	Specifications	Qty.	Unit (No.)	Quoted Unit Price (Rs.)	Total Amount
1	Construction of Permanent Check Dam	As per drawing and estimate		Number		
		Total				
		Taxes@..... % (if any)				
		Grand Total				

Terms and Conditions:

1. GST Number
2. Type of GST
- 3.
4. Composite/Regular Transport
5. Quotation validity
- 6.
7. Warranty/ Guarantee
8. Expiry date of the material (wherever applicable)–
9. ...()...
MSME Registration–Yes/no
Special Remark
10. Any add on service

Signature with Stamp of Firm
Name of Authorized
Signatory

NO.	DESCRIPTION OF WORK	QUANTITY	RATE	UNIT	AMOUNT
(A)	EXCAVATION, FILLING AND SOILING				
A-1	EXCAVATION FOR FOUNDATION In all types of soil, including refilling around foundations & in plinth with selected excavated earth in 200 mm thick layers, watering, consolidating etc. & disposing off surplus earth by spreading at site as directed, complete. (including dewatering if required)				
a)	In earth, all types of soil and soft murrum l) up to 1500 mm depth	3.92		M ³	
b)	In Hard Murrum l) up to 1500 mm depth	27.43		M ³	
c)	In Soft Rock l) up to 1500 mm depth	47.02		M ³	
A-2	Providing and laying DRY TRAP RUBBLE SOLING 200 mm thick, all interstices filled in, thoroughly consolidated and rammed complete, FOR APRON	5.52		M ³	
	Actual Rate Analysis				
(A)	EXCAVATION, FILLING AND SOILING		- TOTAL	RS.	
(B)	CEMENT CONCRETE (PLAIN & REINFORCED)				
B-1	Providing and laying PLAIN CEMENT CONCRETE M-10(1:3:6 nominal mix by volume) in foundation and elsewhere, using trap metal max. 40 mm size, including framework, if any, consolidating, finishing and curing complete. (cement consumption 4.24 bag/m3)	21.82		M ³	
B-2	Providing and laying PLAIN CEMENT CONCRETE M-200 (1:2:4 nominal mix by volume, by using 53 grade cement) in bed-blocks, coping, and elsewhere, using trap metal max. 40 mm size, including framework, if any, consolidating, finishing and curing complete. (cement consumption 6.00 bag/m3)	13.21		M ³	
B-3	Providing, cutting, bending, hooking, binding, placing in position STEEL REINFORCEMENT for all R.C.C. work at all levels, with chairs, supports etc. to provide proper cover complete. (binding wire not to be weighed for payment).				
a)	Mild Steel Plain Round Bars as per Structural details.				
	&				
	Tor Steel Bars as per Structural details.	0.08		M.T.	
	Market rate				
(B)	CEMENT CONCRETE (PLAIN & REINFORCED)		- TOTAL	RS.	
(C)	MASONRY WORK (Concrete1:3:6)				
C-1	Providing and laying PLAIN CEMENT CONCRETE M-100 (1:3:6 nominal mix by volume) in foundation and elsewhere, using trap metal max. 40 mm size, including framework, if any, consolidating, finishing and curing complete. (cement consumption 4.24 bag/m3)	41.62		M ³	
(C)	MASONRY WORK (CONCRETE1:3:6)			RS.	
(D)	MISCELLANEOUS ITEMS				
i.	Providing & fixing in position tor steel bars 16 mm diameter, in foundation including drilling holes in foundation, grouting with cement slurry etc complete.				
ii.	Body wall	27.00		No.	

NO.	DESCRIPTION OF WORK	QUANTITY	RATE	UNIT	AMOUNT
i.	Transverse sill	14.00		No.	
	Actual rate analysis				
ii	Providing & Fixing name plate out of marble slab 25 to 30 mm thick, letters engraved with colour scheme as directed etc complete.	0.27		M ²	
	Market rate				
iii	Transportation of metal lead from 15 km	20.89		Cum.	
iv	Transportation of sand lead from 13 km	46.00		Cum.	
v	Transportation of cement lead from 15 km ,1902, 1903,1904D	23.30		Cum.	
vi	Transportation of masonry stone lead from 8 km	28.20		Cum.	
vii	Transportation of Boulder lead from 8 km	148.04		Cum.	
(D)	MISCELLANEOUS ITEMS		- TOTAL	Rs.	

SCHEDULE OF QUANTITIES AND RATES

*** SUMMARY STATEMENT:**

(A)	EXCAVATION, FILLING AND SOILING		- - -	Rs.	
(B)	CEMENT CONCRETE (PLAIN & REINFORCED)		- - -	Rs.	
(C)	MASONRY WORK (CONCRETE 1:3:6)		- - -	Rs.	
(D)	MISCELLANEOUS ITEMS		- - -	Rs.	
	TOTAL FROM (A) TO (E)			Rs.	
(E)	GST%				
(F)	Contingencies%				
			Say	Rs.	

Plan of Checkdam construction HRDP Project, Jhabua

