

BAIF Institute for Sustainable Livelihoods and Development (BAIF Livelihoods)

BAIF-MITTRA Bhavan, Opp. Niwas Homes, Behind Bodhale Nagar, Nashik-Pune Road, Nashik 422011
Telephone No. 0253-2416057/58 2411745 2411589 E-mail: mittransk@gmail.com

TENDER FOR QUOTATIONS FOR PIPELINE, PUMP, CHAMBERS & ACCESSORIES

O. No. ~~O.No.BISLD/NASHIK~~ 575 / 25

Date: 26.02.2025

You are invited to submit your most competitive quotation for the following products:

Brief Description of the Product	Qty (No.)	Place of Delivery	Expected Month for Delivery of Material & Installation
<u>Site No - 01</u> Pipeline, Pump, Chambers and Accessories (Annexure - A, B & C)	02	Village: Guhir Tal. Wada Dist. Palghar	March 2025
<u>Site No -02</u> Pipeline, Pump, Chambers and Accessories (Annexure - A, B, & C)			

Detailed Description of the Product - PIPELINE, PUMP, CHAMBERS & ACCESSORIES

As above

1. Quoted Price:

- The contract shall be for valid up to 30.03.2025 for the above described products.
- The bidder shall quote for goods / services in the attached format of quotation.
- All duties, taxes, F.O.R. and other levies payable by the bidder shall be included in the goods/services and shall stand final.
- The rates quoted for each good/service shall be fixed for the duration of the contract and shall not be subject to adjustment.
- Corrections if any, shall be made by crossing out, initialing, dating and rewriting.
- The prices shall be quoted in Indian Rupees only
- The work quantity may vary.
- Estimate is subject to change in future orders
- Bidder has to mentioned location (s) of work where service can be provided.
- Preferred vendors should have experience in similar types of work (Experience Certificate to be submitted as proof).

2. Each bidder must submit only one quotation. Bidder shall not contact other bidders in matters related to this Quotation.

3. Validity of Quotations:

The quotation shall remain valid up to 30.03.2025 after the deadline fixed for submission of quotations.

4. Evaluation of Quotations:

Purchaser will evaluate and compare the quotations determined to be substantially responsive i.e. which are properly signed and conform to the terms and conditions and specifications in the following manner.

- a. The evaluation will be done exclusive of GST.
- b. The evaluation would be done for all the goods/services put together. The items for which no rates have been quoted would be treated as zero and the total amount would be computed accordingly. We will award the contract to the responsive bidder whose total cost for all the items put together is the lowest.
- c. Compare terms & conditions and specifications

5. Award of contract:

- a. Purchaser will award the contract to the bidder whose quotation has been determined to be substantially responsive and who has offered the lowest price as per Para 4 (b) above.
- b. Purchaser prior to the expiry of the validity period of the quotation will notify the bidder whose quotation has been accepted for award of contract. The terms of the accepted offer shall be incorporated in the Purchase Order or Work Order.
- c. Notwithstanding the above, the purchaser reserves the right to accept or reject any quotation and to cancel the bidding process and reject all quotations any time prior to the award of the contract.

6. Payment shall be made 15 days after receipt and installation as per required of Pipeline, Pump, Chambers and Accessories

7. Normal commercial guarantee / warranty shall be applicable to the supplied goods and its installation.

8. Cost of Procurement Processing:

The bidder shall pay a "Tender Fee "of **Rs.500/-** only through Bhim UPI VPA / QR Code. Detailed process is enclosed as Annexure. Prior to submission of Bid, Transaction No. and date are to be mentioned while submitting the bid/quotation.

9. Earnest Money Deposit:

EMD for this tender will be 2% of the total cost of the PO. BAIF Livelihoods Nashik will compare all the bids and the Purchase Committee will award a contract to the selected Vendor. The selected Vendor will be informed of the selection for supply of goods/services by E-mail. The selected Vendor has to transfer the EMD amount within two working days and inform the Transaction No. and date by return E-mail. After confirmation of EMD amount being deposited in BAIF Livelihoods Bank Account, BAIF Livelihoods will issue the Purchase Order/Work Order. In case of failure to pay EMD, BAIF Livelihoods Purchase Committee reserves the right to decide further course of action. The same will be refunded (interest free) after obtaining the work completion report of the total scope of work or guarantee/warranty period, for at least one monsoon season period whichever is applicable. The earnest money shall be liable to be forfeited, if the successful bidder, after submitting the tender rescinds from or modifies the offer after acceptance of the tender.

After acceptance of Work Order/Purchase Order and payment of EMD, if work is not completed or material is not supplied within the validity period of the Work Order/Purchase Order, the Vendor will not be eligible for refund of EMD and will also not be eligible to participate in future tender process of BAIF Livelihoods for a period of one year.

Submission of Quotations:

- Sealed Envelope mentioning "**Pipeline, Pump, Chambers and Accessories**" on it.
- Transaction No. and date for payment of tender fee.
- The quotation should be accompanied by a government approved/registered agency certificate
- List of Similar Works Undertaken with details of clients etc. if any.
- **Last date of Submission is 06-03-25** latest by 5:30 pm.
- Address: **Purchase Department, BAIF Livelihoods, BAIF-MITTRA Bhavan, Opp. Niwas Homes, Behind Bodhale Nagar, Nashik Pune Road, Nashik 422011**

We look forward to receiving your quotation.

Yours sincerely



(Dr. Raviraj Jadhav)
Regional Director
BAIF Livelihoods

Encl.: Format of Quotation

(To be printed on Pre-numbered Quotation format or if same is not available then on Letterhead with unique number and date)

FORMAT OF QUOTATION

Sr. No.	Description of Goods	Specifications	Qty.	Unit	Quoted Unit Price(Rs.)	Total Amount(Rs.)
		Total				
		Taxes @% (if any)				
		Grand Total				

Terms and Conditions:

1. Tax Registration Number -
2. Transport -
3. Validity of Quotation -
4. Warranty/Guarantee -
5. Expiry date of the material (wherever applicable) -
6. MSME Registration - Yes/No

Tender fees & EMD amount Collection

1. This is to be used for payment from Scan QR Code of BHIM UPI Mobile App / any bank mobile app / Paytm / Google



2. BHIM UPI VPA: bisld@icici

1. After making the payment, the vendor/bidder will receive an online receipt, as well as the Transaction No. as confirmation of payment
2. Vendor / Bidder has to inform the “Transaction No.” and “Amount” to the Purchase Dept. Nashik immediately through E-mail and also at the time of submitting the quotation in case of Tender Fee and before receiving PO / WO in case of EMD.

Site No - 01

BAIF INSTITUTE FOR SUSTAINABLE LIVELIHOODS AND DEVELOPMENT, NASHIK					
Name of Project - SPREADING HAPPINESS INDIYA FOUNDATION					
Name of work - Pipeline, Pump, Chambers and Accessories					
Name of village - Guhir, Tal. Wada, Dist. Palghar.					
Quotation for Pipeline, Pump, Chambers and Accessories (Annexure- A, B & C)					
Annexure - A - Pipeline and Accessories					
Sr. No.	Activity	Qty.	Unit	Rate	Amt. in Rs.
1	Excavation of deep trenches for laying and raising the main in Earth Soil of all types, sand, gravel and soft murum including trimming to correct line, level and to specified widths including removing the excavated material and stacking or spreading the same up to a distance of 1400m main line and Distribution line 2500 m and all lifts as directed, preparing the bed for foundation and necessary safety precautions. Keep the trench undisturbed till pipe laying & fixing necessary specials etc are complete as per detailed specifications and as directed (payable measurements with vertical excavation).	789.75	Cum		
2	Excavation of deep trenches for laying and raising main in Hard murum, soft bhisra, Hard man and boulder including trimming to correct line and level and to specified width, including removing the excavated material and stacking or spreading the same up to a distance of 1400m main line and Distribution line 2500m and all lifts as directed, preparing the bed for foundation and necessary safety precautions. Keep the trench undisturbed till pipe laying and fixing necessary specials etc are complete as per detailed specifications (payable measurements with vertical excavation).	631.80	Cum		
3	Excavation of deep trenches for laying and raising main in Hard Rock of any toughness by breaker to correct line and level and to specified width including trimming and levelling the bed as directed. Removing the excavated material and sorting, stacking the same up to a distance of 1400m main line and Distribution line 2500m and all lifts as directed, preparing the bed for foundation and keeping the trench undisturbed till pipe laying and fixing necessary specials etc are completed as per detailed specifications and as directed. (payable measurements with vertical excavation).	157.95	Cum		

BAIF INSTITUTE FOR SUSTAINABLE LIVELIHOODS AND DEVELOPMENT, NASHIK					
Name of Project - SPREADING HAPPINESS INDIYA FOUNDATION					
Name of work - Pipeline, Pump, Chambers and Accessories					
Name of village - Guhir, Tal. Wada, Dist. Palghar.					
Quotation for Pipeline, Pump, Chambers and Accessories (Annexure- A, B & C)					
Annexure - A - Pipeline and Accessories					
Sr. No.	Activity	Qty.	Unit	Rate	Amt. in Rs.
4	Providing and laying Murum bedding using available material from excavation in trenches with murum of approved quality in layers not exceeding 150 mm to 200mm, each layer shall be compacted by watering and ramming etc and completed as directed.	263.25	Cum		
5	Providing and supplying in standard lengths Polyethylene Pipe, conforming to IS 4984/14151/12786/ 13488 with necessary jointing material like mechanical connector i. e. thread / insert joint / quick release coupler joint / compression fitting joint or flanged joint excluding coupler/specials, including transportation from stores to site of work, inspection charges, excluding GST levied by GI & GOM in all respect. As per IS: 4984-2016, the pipes up to 110mm dia. should be supplied in coil form only.				
	125 mm, H. D. P. E. pipes PE 80 - 4 kg/sqm - Make Jain/Finolex	1400	RM		
	90 mm, H. D. P. E. pipes PE 80 - 6 kg/sqm - Make Jain/Finolex	50	RM		
6	Lowering, Laying and Jointing H.D.P.E./M.D.P.E. pipes in proper position including all specials by electro fusion and butt fusion jointing procedure as per relevant IS Code complete with all materials for jointing procedure like Electro fusion machine, Electric heater/butt fusion welding machine with hydraulic jack, top loading clamp etc. and all labours as directed by Engineer-in-Charge as per IS-7634 Part II				
	Lowering & Laying H. D. P. E. pipes for all classes and pressure.				
	125 mm, H. D. P. E. pipes PE 80 - 4 kg/sqm - Make Jain/Finolex	1400	RM		
	90 mm, H. D. P. E. pipes PE 80 - 6 kg/sqm - Make Jain/Finolex	50	RM		

BAIF INSTITUTE FOR SUSTAINABLE LIVELIHOODS AND DEVELOPMENT, NASHIK					
Name of Project - SPREADING HAPPINESS INDIYA FOUNDATION					
Name of work - Pipeline, Pump, Chambers and Accessories					
Name of village - Guhir, Tal. Wada, Dist. Palghar.					
Quotation for Pipeline, Pump, Chambers and Accessories (Annexure- A, B & C)					
Annexure - A - Pipeline and Accessories					
Sr. No.	Activity	Qty.	Unit	Rate	Amt. in Rs.
7	Providing and supplying in standard lengths ISI mark rigid unplasticized PVC pipes suitable for potable water with solvent cement joints including cost of couplers, as per IS specification no. 4985 / 1988 excluding GST levied by GOI and GOM in all respect, including transportation, freight charges, inspection charges, loading, unloading, conveyance to the departmental stores and stacking the same in closed shed duly protected from sun rays and rains including cost of jointing material i.e. Solvent cement, etc. complete (self-fit type to be jointed with cement solvent).				
	90 mm, 4 kg. / Sq. cm - Make Jain/Finolex	2500	RM		
8	Lowering, laying and jointing with P.V.C. pipes and specials of following class and diameter including cost of conveyance from stores to site of works including cost of all labour, material, except cement solvent, rubber ring, as per IS code, etc. complete (with cement solvent joint / ring fit joint).				
	90 mm, 4kg. / Sq. cm - Make Jain/Finolex	2500	RM		
9	Providing and supplying ISI mark CI D/F reflux valves (non-return valves) of following dia including transportation from stores to site of work, inspection charges, excluding GST levied by GOI & GOM in all respect etc. complete. Reflux valves as per IS.5312 Part I (1984) a) without bypass arrangement PN -1				
	100 mm	1	No.		
10	Lowering, laying and jointing in position following C.I.D/F Reflex valves (non-return valves), Butterfly valves and Sluice valves including cost of all labour jointing material, including nut bolts and giving satisfactory hydraulic testing etc. complete (Rate for all class of valves.) with brick work chamber.				

BAIF INSTITUTE FOR SUSTAINABLE LIVELIHOODS AND DEVELOPMENT, NASHIK					
Name of Project - SPREADING HAPPINESS INDIYA FOUNDATION					
Name of work - Pipeline, Pump, Chambers and Accessories					
Name of village - Guhir, Tal. Wada, Dist. Palghar.					
Quotation for Pipeline, Pump, Chambers and Accessories (Annexure- A, B & C)					
Annexure - A - Pipeline and Accessories					
Sr. No.	Activity	Qty.	Unit	Rate	Amt. in Rs.
	100 mm	1	No.		
11	Providing and supplying Air Valves as per IS14845-2000 and MJP's standard specifications of approved make and quality of following diameters including inspection charges, transportation from stores to site of work excluding GST levied by GOI & GOM in all respect etc. complete. with brickwork chamber				
	25 mm	6	No.		
12	Lowering, laying and fixing in proper alignment and position all types of C.I. air valves as directed by Engineer-in-charge including cost of conveyance from stores to site of work, cost of all material and giving satisfactory hydraulic testing etc. complete (for all class of valves).				
	25 mm	6	No.		
13	Providing and laying Cast in situ / Ready Mix cement concrete in M15 of trap / granite / quartzite / gneiss metal for foundation and bedding /steps including steel cantering, form work, laying /pumping, compacting, roughening them if special finish is to be provided, finishing un even and honey combed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honey combed surface, only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden cantering will not be allowed.), etc. complete with fine aggregate (Crushed sand VSI Grade).	0.51	Cum		
14	Providing, supplying, lowering, laying and fixing Cast Iron ISI Mark Ball Valve/ Control Valve, 3 feet barrel & G.I Bend on top etc. as required.				
	100 mm	10	No.		

BAIF INSTITUTE FOR SUSTAINABLE LIVELIHOODS AND DEVELOPMENT, NASHIK					
Name of Project - SPREADING HAPPINESS INDIYA FOUNDATION					
Name of work - Pipeline, Pump, Chambers and Accessories					
Name of village - Guhir, Tal. Wada, Dist. Palghar.					
Quotation for Pipeline, Pump, Chambers and Accessories (Annexure- A, B & C)					
Annexure - A - Pipeline and Accessories					
Sr. No.	Activity	Qty.	Unit	Rate	Amt. in Rs.
15	Providing and fixing heavy duty PVC Sluice valve including T, jointing including all accessories, transportation up to departmental store, unloading, stacking excluding GST levied by GOI & GOM in all respect etc. complete.				
	90 mm	40	No.		
16	Providing & Fixing Water meter for main pipeline on 125mm HDPE pipe. TEP 50 mm Woltmann Water Meters, TES.WAT.61101727, Conforms to ISO 4064, Class-b,	1	No.		
17	Refilling the trenches with available excavated stuff with soft material first over pipeline and then hard material in 15 cm layers with all leads and lifts including consolidation, etc. complete.				
	Total Quantity	1285.635	Cum		
	Total Amount, Rs-				
	GST% Rs-				
	Total Amount with GST, Rs-				

Annexure - B - Pump and Accessories					
Sr.No.	AC Submersible Pumping system	Unit	Qty (Set)	Unit Price	Total Amt. (Rs.)
1	Providing And Fixing Submersible AC Pump & Motor- 7.50 HP, 12.92 LPS (775 LPM) for 36m Head, With 5 Year Warranty, Model No: -LHL 9BG Kirloskar make with ISI Mark.	nos	1		
	Total Amount, Rs-				
	GST% Rs-				
	Total Amount with GST, Rs.				

Annexure - C - Chambers and Accessories					
Sr.No.	Particulars	Quantity	Unit	Unit Rate	Amount, Rs.
1	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete (Lift up to 0.00 to 1.50 m.) manually.	1.73	Cum		
2	Providing and laying Cast in situ/Ready Mix cement concrete in M-10 of trap/ granite/ quartzite/ gneiss metal for foundation and bedding including bailing out water, Steel cantering, framework, laying/pumping, compacting, roughening them if special finish is to be provided, finishing if required and curing complete, with fully automatic microprocessor-based PLC with SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer) etc. complete with fine aggregate (Crushed sand VSI Grade).	0.14	Cum		
3	Providing dry/ trap / granite / quartzite / gneiss rubble stone soling 15 cm to 20 cm thick including hand packing and compacting etc. complete.	0.29	Cum		
4	Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in foundations and plinth of inner walls/ in plinth external walls including bailing out water manually, striking joints on unexposed faces, raking out joints on exposed faces and watering etc. complete.	0.80	Cum		
5	Providing and fixing with coping Heavy-Duty Manhole Cover for All Purposes Chamber Cover Sump Cover Water Tank Cover 1 Ton Capacity with Locking System (1m x 1m size) with angle frame 50x50x5mm and 2mm GI sheet cover with fix hinges and locking system.	1.00	No.		
	Quotation for 01 chamber is Rs. (Sr. No.1+2+3+4+5)				
	Quotation for 10 Chambers is Rs.	10	No.		
	GST% Rs-				
	Total Amount with GST, Rs-				

Site No. - 02

BAIF INSTITUTE FOR SUSTAINABLE LIVELIHOODS AND DEVELOPMENT, NASHIK					
Name of Project - SPREADING HAPPINESS INDIYA FOUNDATION					
Name of work - Pipeline, Pump, Chambers and Accessories					
Name of village - Gohar, Tal. Wada, Dist. Palghar.					
Quotation for Pipeline, Pump, Chambers and Accessories (Annexure- A, B & C)					
Annexure - A - Pipeline and Accessories					
Sr. No.	Activity	Qty.	Unit	Rate	Amt. Rs.
1	Excavation for deep trenches for laying, raising main in Earth Soil of all types, sand, gravel and soft murum including trimming to correct line, level and to specified widths including removing the excavated material and stacking or spreading the same up to a distance and all lifts as directed, preparing the bed for foundation and necessary safety precautions, keep the trench undisturbed till pipe laying & fixing necessary specials etc complete as per detailed specifications and as directed (payable measurements with vertical excavation).	761.40	Cum		
2	Excavation for deep trenches for laying rising main in Hard murum, soft bhisra, Hard man and boulder including trimming to correct line and level and to specified width, including removing the excavated material and stacking or spreading the same up to a distance and all lifts as directed, preparing the bed for foundation and necessary safety precautions, keep the trench undisturbed till pipe laying and fixing necessary specials etc complete as per detailed specifications (payable measurements with vertical excavation).	609.12	Cum		
3	Excavation for deep trenches for laying rising main in Hard Rock of any toughness by breaker to correct line and level and to specified width including trimming and levelling the bed as directed, removing the excavated material and sorting, stacking the same up to a distance and all lifts as directed, preparing the bed for foundation and keep the trench undisturbed till pipe laying & fixing necessary specials etc complete as per detailed specifications and as directed (payable measurements with vertical excavation).	152.28	Cum		
4	Providing and laying Murum bedding using available material from excavation in trenches with murum of approved quality in layers not exceeding 150 mm to 200mm, each layer shall be compacted by watering and ramming etc complete as directed.	253.80	Cum		

BAIF INSTITUTE FOR SUSTAINABLE LIVELIHOODS AND DEVELOPMENT, NASHIK					
Name of Project - SPREADING HAPPINESS INDIYA FOUNDATION					
Name of work - Pipeline, Pump, Chambers and Accessories					
Name of village - Gohar, Tal. Wada, Dist. Palghar.					
Quotation for Pipeline, Pump, Chambers and Accessories (Annexure- A, B & C)					
Annexure - A - Pipeline and Accessories					
Sr. No.	Activity	Qty.	Unit	Rate	Amt. Rs.
5	Providing and supplying in standard lengths Polyethylene Pipe, confirming to IS 4984/14151/12786/ 13488 with necessary jointing material like mechanical connector i. e. thread / insert joint / quick release coupler joint / compression fitting joint or flanged joint excluding coupler/specials, including transportation from stores to site of work, inspection charges, excluding GST levied by GI & GOM in all respect. As per IS: 4984-2016, the pipes up to 110 mm dia. should be supplied in coil form only.				
	Providing H. D. P. E. pipes PE 80				
	125 mm, H. D. P. E. pipes PE 80 - 4 kg/sqm - Make Jain/Finolex	1110.00	RM		
	90 mm, H. D. P. E. pipes PE 80 - 6 Kg/sqm - Make Jain/Finolex	50.00	RM		
6	Lowering, Laying and Jointing H.D.P.E./M.D.P.E. pipes in proper position including all specials by electro fusion and butt fusion jointing procedure as per relevant IS Code complete with all materials for jointing procedure like Electro fusion machine, Electric heater/butt fusion welding machine with hydraulic jack, top loading clamp etc. and all labours as directed by Engineer-in-Charge as per IS-7634 Part II				
	Lowering & Laying H. D. P. E. pipes for all classes and pressure				
	125 mm, H. D. P. E. pipes PE 80 - 4 kg/sqm - Make Jain/Finolex	1110.00	RM		
	90 mm, H. D. P. E. pipes PE 80 - 6 kg/sqm - Make Jain/Finolex	50.00	RM		
7	Providing and supplying in standard lengths ISI mark rigid unplasticized PVC pipes suitable for potable water with solvent cement joints including cost of couplers, as per IS specification no. 4985 / 1988 excluding GST levied by GOI and GOM in all respect, including transportation, freight charges, inspection charges, loading, unloading, conveyance to the departmental stores and stacking the same in closed shed duly protected from sun rays and rains including cost of jointing material i.e. Solvent cement, etc. complete (self-fit type to be jointed with cement solvent).				
	90 mm, 4 kg / Sq. cm - Make Jain/Finolex	2650	RM		
8	Lowering, laying and jointing with P.V.C. pipes and specials of following class and diameter including cost of conveyance from stores to site of works including cost of all labour, material, except cement solvent, rubber ring, as per IS code, etc. complete with cement solvent joint / ring fit joint.				
	90 mm, 4kg. / Sq. cm - Make Jain/Finolex	2650	RM		

BAIF INSTITUTE FOR SUSTAINABLE LIVELIHOODS AND DEVELOPMENT, NASHIK					
Name of Project - SPREADING HAPPINESS INDIYA FOUNDATION					
Name of work - Pipeline, Pump, Chambers and Accessories					
Name of village - Gohar, Tal. Wada, Dist. Palghar.					
Quotation for Pipeline, Pump, Chambers and Accessories (Annexure- A, B & C)					
Annexure - A - Pipeline and Accessories					
Sr. No.	Activity	Qty.	Unit	Rate	Amt. Rs.
9	Providing and supplying ISI mark CI D/F reflux valves (non-return valves) of following Dia including transportation from stores to site of work, inspection charges, excluding GST levied by GOI & GOM in all respect etc. complete. Reflux valves as per IS.5312 Part I (1984) a) Without bypass arrangement PN -1				
	100 mm	1.00	No.		
10	Lowering, laying and jointing in position following C.I.D/F Reflex valves (non-return valves), Butterfly valves and Sluice valves including cost of all labour jointing material, including nut bolts and giving satisfactory hydraulic testing etc. complete. (Rate for all class of valves.) with brick work chamber				
	100 mm	1.00	No.		
11	Providing and supplying Air Valves as per IS14845-2000 and MJP's standard specifications of approved make and quality of following diameters including inspection charges, transportation from stores to site of work excluding GST levied by GOI & GOM in all respect etc. complete with brickwork chamber.				
	25 mm	5.00	No.		
12	Lowering, laying and fixing in proper alignment and position all types of C.I. air valves as directed by Engineer-in-Charge including cost of conveyance from stores to site of work, cost of all material and giving satisfactory hydraulic testing etc. complete (for all class of valves).				
	25 mm	5.00	No.		
13	Providing and laying Cast in situ / Ready Mix cement concrete in M15 of trap / granite / quartzite / gneiss metal for foundation and bedding /steps including steel centering, form work, laying /pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honey combed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honey combed surface, only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc (wooden centering will not be allowed.) complete with fine aggregate (Crushed sand VSI Grade).	0.43	Cum		
14	Providing, supplying, lowering, laying and fixing Cast Iron ISI Mark Ball Valve/ Control Valve, 3 feet barrel & G.I Bend on top as required.				

BAIF INSTITUTE FOR SUSTAINABLE LIVELIHOODS AND DEVELOPMENT, NASHIK					
Name of Project - SPREADING HAPPINESS INDIYA FOUNDATION					
Name of work - Pipeline, Pump, Chambers and Accessories					
Name of village - Gohar, Tal. Wada, Dist. Palghar.					
Quotation for Pipeline, Pump, Chambers and Accessories (Annexure- A, B & C)					
Annexure - A - Pipeline and Accessories					
Sr. No.	Activity	Qty.	Unit	Rate	Amt. Rs.
	100 mm	12.00	No.		
15	Providing and fixing heavy duty PVC Sluice valve including T, jointing including all accessories, transportation up to departmental store, unloading, stacking excluding GST levied by GOI & GOM in all respect etc. complete.				
	90 mm	30.00	No.		
16	Providing & Fixing Water meter for main pipeline on 125mm HDPE pipe. TEP 50 mm Woltmann Water Meters, TES.WAT.61101727, Conforms to ISO 4064, Class-b,	1.00	No.		
17	Refilling the trenches with available excavated stuff with soft material first over pipeline and then hard material in 15 cm layers with all leads and lifts including consolidation, etc. complete.				
	Total Quantity	1268.70	Cum		
	Total Amount, Rs-				
	GST% Rs-				
	Total Amount with GST, Rs-				
Annexure - B - Pump and Accessories					
Sr. No.	AC Submersible Pumping system	Unit	Qty (Set)	Unit Price	Total Amount (Rs.)
1	Providing And Fixing Submersible AC Pump & Motor- 7.50 HP, 15.67 LPS (940 LPM) for 26m Head, with 5 Year Warranty, Model No.: -LHL 9BG Kirloskar make with ISI Mark.	Nos	1		
	Total Amount, Rs-				
	GST% Rs-				
	Total Amount with GST, Rs-				

Annexure - C - Chambers and Accessories

Sr. No.	Particulars	Qty.	Unit	Unit Rate	Amt. in Rs.
1	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete (lift up to 0.00 to 1.50 m.) manually.	1.73	Cum		
2	Providing and laying Cast in situ/Ready Mix cement concrete in M-10 of trap/ granite/ quartzite/ gneiss metal for foundation and bedding including bailing out water, Steel centering, framework, laying/pumping, compacting, roughening them if special finish is to be provided, finishing if required and curing complete, with fully automatic microprocessor-based PLC with SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer) etc. complete with fine aggregate (Crushed sand VSI Grade).	0.14	Cum		
3	Providing dry/ trap/ granite/ quartzite/ gneiss rubble stone soling 15 cm to 20 cm thick including hand packing and compacting etc. complete.	0.29	Cum		
4	Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in foundations and plinth of inner walls/ in plinth external walls including bailing out water manually, striking joints on unexposed faces, raking out joints on exposed faces and watering etc. complete.	0.80	Cum		
5	Providing and fixing with coping Heavy-Duty Manhole Cover for All Purposes Chamber Cover Sump Cover Water Tank Cover 1 Tons Capacity with Locking System (1m x 1m Size) with angle frame 50x50x5mm and 2mm GI sheet cover with fix hinges and locking system.	1.00	No.		
	Quotation for 01 chamber is Rs. (Sr.1+2+3+4+5)				
	Quotation for 12 Chamber is Rs.	12	No.		
	GST% Rs-				
	Total Amount with GST Rs.				